No.	Item of work	Unit	Rate	Cost	Rate to be quoted in	
					Figures	Words
			Rs. a. p.			
12	Constructing round pillars of 1′ dia. with burnk bric in mortar of wire cut quadrant shaped bricks with base and capital as per design, including intermediate bond slabs at 3 ft. apart with plastering, etc., complete	R.ft.	1 0 0	50		
13	Plastering with lime mortar	Sqr.	2 8 0	36.14		
14	Flooring with 1½″ of cement concrete over 3″ of lime concrete and ½″ of cement plaster mixed with red ochre and lines cut to tile pattern	Sqr.	20 0 0	13.00		
15	Burnt brick in mortar	R.ft.	0 8 0	199		
16	Plain cornice as per design	R.ft.	0 4 0	199		
17	Providing R.C.C chajjas over windows 5″ to 6″ thick and tapering to 3″ at end with proper reinforcements, etc. ..	Sqr.	60 0 0	5.04		
18	Cement pointing to basement	,,	3 0 0	4.00		
19	Painting with Lac Factory green paint two coats	,,	3 8 0	9.76		
20	Providing reinforced cement concrete beam for the front verandah	R.ft.	2 8 0	52		
21	R.C.C. square ventilators as per design ..	Each	0 12 0	8		
22	Teakwood screen with panels including fixing and painting	S.ft.	1 0 0	160		

M. K. RAJAM IYENGAR,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 28th June 1940.

The attention of the public is invited to the detailed notification dated 28th June 1940, published on pages 1573—1576, Part VI of the *Mysore Gazette*, dated 4th July 1940, regarding tenders for restoring Ramachandrapura Jadayyanakere Tank, Regd. No. 648 (unrestored minor tank), of Mulbagal Taluk.

The last date for lodging of tender is up to 2 P.M. on 22nd July 1940.

Abstract Notification dated 5th July 1940.

The attention of the public is invited to the detailed notification dated 2nd July 1940, published on pages 1630-1633, Part VI of the *Mysore Gazette*, dated 11th July 1940, regarding tenders for restoring Kambalahalli Byrasettikere, Reg. No. 73 of Chickballapur Taluk.

The last date for lodging of tender is upto 2 P.M. on 27th July 1940.

Abstract Notification dated 5th July 1940.

The attention of the public is invited to the detailed notification dated 4th July 1940, published on pages 1633-1635, Part VI of the *Mysore Gazette*, dated 11th July 1940, regarding tenders for restoring Kavatanahalli Nagarkunte, R. No. 110 of Mulbagal Taluk, Sl. No. 76, (unrestored Minor Tank).

The last date for lodging of tender is upto 2 P.M. on 26th July 1940.

Abstract Notification dated 5th July 1940.

The attention of the public is invited to the detailed notification dated 4th July 1940, published on pages 1636-1638, Part VI of the *Mysore Gazette*, dated 11th July 1940, regarding tenders for restoring Kavarnahalli Tank, Reg. No. 193, (unrestored Minor) in Chickballapur Taluk.

The last date for lodging of tender is upto 2 P.M. on 29th July 1940.

Notification dated 13th July 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 3rd August 1940, for restoring Pullukuntalahalli Chikkere tank, Reg. No. 159 (unrestored minor tank), Mulbagal Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Pullukuntalahalli Chikkere tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 185, paid to the treasury to the credit of "17 (*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division, Kolar. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 3rd August 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings, may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of March 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum

on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form.

Abstract estimate for restoring Pullukuntalahalli Chikkere, Reg. No. 159 of Mulbagal Taluk, (unrestored minor tank).

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	I. *Bund at R. L.* 56.00.				
1	Clearing thick jungle with roots	Grade	2 0 0	15	
2	Removing ant-hills and filling the same with sand	Each	1 0 0	9	
3	Earthwork excavation, cutting grips and trenches for the seat of new earthwork	Grade	2 0 0	15	
4	Earthwork excavation to bund from barrow pits with lead and lift including watering and consolidation, etc., complete	C.yds.	0 3 0	7,675	
5	Turfing to slopes of bund	S.yd.	0 0 9	5,026	
6	Removing and resetting the bulged out revetment with new jelly backing and wedging, etc., complete	C.yd.	0 8 0	198	
7	Constructing new rough stone revetment with new jelly backing and wedging including 1 mile lead and lift, complete	C.yd.	1 8 0	583	

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs. a. p.
8	Providing and fixing new grade stones including carving figures and painting with bed slabs, etc., complete	Each	1 8 0	23	
9	Do Index stones do ..	,,	0 6 0	23	
10	Do Reg. No. stones do ..	,,	3 0 0	1	
11	Do B. M. stones do ..	,,	2 8 0	2	
	Total Rs.				
	II. *Constructing a new 6″ dia. C. I. pipe sluice at C. S. 3 with Cill at 43.00.*				
1	Earthwork cutting open the bund and refilling the same with watering and consolidation complete	C.yd.	0 5 0	44	
2	Burnt stone jelly concrete in surki mortar (1: 1: 1: 4)	C.ft.	0 4 0	49	
3	Burnt size stone in surki mortar ..	,,	0 4 6	313	
4	Providing and fixing burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 6	52	
5	Cement pointing after raking joints ¾″ to 1″ deep (1 : 3 prop.)	Sqr.	3 8 0	2.40	
6	Providing and fixing C. I. pipes of 6″ dia. with Railway freight, carting to site, etc., complete ..	R.ft.	3 0 0	36	
7	Providing and fixing a new plug and rod with locking arrangement, etc., complete ..	Each.	15 0 0	1	
	Total Rs. ..				
	III. *Constructing a masonry weir at R. L. 51·00 Long 85 feet.*				
1	Earthwork excavation foundation and using the earth to bund with watering and consolidation with lead and lift, etc., complete	C.yd.	0 3 0	63	
2	Burnt stone jelly concrete in surki mortar (1 : 1 : 1 : 4)	C.ft.	0 4 0	158	
3	Burnt size stone in surki mortar	,,	0 4 6	610	
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 6	216	
5	Cement pointing after raking joints ¾″ to 1″ deep (1 : 3 prop.)	Sqr.	3 8 0	7.00	
6	Constructing new rough stone apron and wings with new jelly backing and wedging including lead of 1 mile and lift, etc., complete ..	C.yds.	1 8 0	75	
	Total Rs. ..				

C. R. IYENGAR,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 9th July 1940.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 31st July 1940, for constructing a building for Restaurant in the Law Courts Building, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of four annas only for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing a building for Restaurant in Law Courts Building, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 257 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for due fulfilment